5	Construction of granular sub-base by providing close graded material, mixing in mechaical mix plant at OMC carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density Complete as per specification and direction of Engineer-in-charge of the work.	Cum	973.5	1060.56	Rupees One Thousand Sixty and Fifty Six Paise Only
6	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work.	Cum	1622.5	1121.04	Rupees One Thousand One Hundred Twenty One and Four Paise Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.	Cum	2496.5	72.71	Rupees Seventy Two and Seventy One Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BANGALORE-560 010

Signature of the Contractor

EXECUTIVE ENGINEER
Executive Engineer
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Division,
Dasarahalli Zone, Bangalore-57.

Scanned by CamScanner